ARCHITECTURAL DRAWING

SCALE: 1:100

SHEET NO. A-01

DATE: 14/03/2024

DRAWN BY: M. KAPOOR

CHECKED BY: S. DESAI

REVISION: R2

PROJECT: RESIDENTIAL BUILDING

CLIENT: MR. & MRS. KAPOOR

LOCATION: PLOT NO. 12, SECTOR 4

NOTES:

1. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS OTHERWISE STATED.
2. DO NOT SCALE FROM THIS DRAWING.
3. REFER TO STRUCTURAL DRAWINGS FOR COLUMN AND BEAM SIZES.
4. ALL WORK TO BE CARRIED OUT AS PER RELEVANT BUILDING CODES.
5. CONTRACTOR TO VERIFY ALL DIMENSIONS ON SITE BEFORE COMMENCING WORK.
6. ANY DISCREPANCY TO BE REPORTED TO THE ARCHITECT IMMEDIATELY.
7. ALL DOORS AND WINDOWS TO BE AS PER SCHEDULE.
8. FLOOR FINISHES TO BE AS SPECIFIED IN THE FINISH SCHEDULE.
9. ALL EXTERNAL WALLS TO BE 230 MM THICK UNLESS NOTED.
10. INTERNAL PARTITION WALLS TO BE 115 MM THICK UNLESS NOTED.
11. PROVIDE DAMP PROOF COURSE AT PLINTH LEVEL.
12. ALL STAIRS TO HAVE NOSING AS SHOWN IN DETAIL.
13. RAILINGS TO BE PROVIDED AS PER SAFETY REGULATIONS.
14. ELECTRICAL AND PLUMBING LAYOUTS TO BE COORDINATED WITH RESPECTIVE CONSULTANTS.
15. ALL SANITARY FIXTURES TO BE AS SELECTED BY THE CLIENT.
16. PROVIDE EXHAUST FANS IN ALL TOILETS AND KITCHEN.
17. ALL OPENINGS IN SLABS TO BE COORDINATED WITH MEP DRAWINGS.
18. PROVIDE WATERPROOFING TO ALL TOILETS AND TERRACES.
19. ALL CONCRETE TO BE OF GRADE M25 UNLESS OTHERWISE SPECIFIED.
20. REINFORCEMENT TO BE HYSD BARS CONFORMING TO IS 1786.
21. PROVIDE ANTI-TERMITE TREATMENT TO ALL FOUNDATIONS.
22. BACKFILLING TO BE DONE WITH APPROVED MATERIAL IN LAYERS.
23. ALL MASONRY TO BE LAID IN CEMENT MORTAR 1:6.
24. PLASTERING TO BE DONE AFTER CURING OF MASONRY FOR 7 DAYS.
25. PROVIDE CONTROL JOINTS AT 4.5 M C/C MAXIMUM.
26. ALL EXPOSED CONCRETE SURFACES TO BE FINISHED SMOOTH.
27. PROVIDE WEATHER COURSE ON TERRACE AS PER DETAIL.
28. ALL METAL WORK TO BE PAINTED WITH TWO COATS OF PRIMER AND TWO COATS OF ENAMEL.
29. PROVIDE MOSQUITO MESH TO ALL OPENINGS.
30. ALL GLASS TO BE 5 MM THICK UNLESS NOTED.
31. PROVIDE CURTAIN RODS TO ALL WINDOWS AND DOORS.
32. ALL HARDWARE TO BE AS SELECTED BY THE ARCHITECT.
33. PROVIDE LETTER BOX AT MAIN ENTRANCE.
34. PROVIDE NAME PLATE AT MAIN ENTRANCE.
35. ALL WORK TO BE DONE IN A WORKMANLIKE MANNER.
36. CONTRACTOR TO KEEP SITE CLEAN AND TIDY DURING CONSTRUCTION.
37. ALL MATERIALS TO BE APPROVED BY THE ARCHITECT BEFORE USE.
38. SAMPLES OF ALL MATERIALS TO BE SUBMITTED FOR APPROVAL.
39. ANY DEVIATION FROM THE DRAWINGS TO BE APPROVED IN WRITING.
40. ALL LEVELS TO BE CHECKED ON SITE BEFORE CONSTRUCTION.
41. PROVIDE TEMPORARY SUPPORTS WHERE NECESSARY.
42. ALL WORK TO BE INSPECTED AT EACH STAGE BEFORE PROCEEDING.
43. PROVIDE AS-BUILT DRAWINGS AFTER COMPLETION.
44. ALL DISPUTES TO BE SETTLED AMICABLY.
45. THIS DRAWING IS THE PROPERTY OF THE ARCHITECT.
46. ALL RIGHTS RESERVED.
47. REVISION R2 INCORPORATES CHANGES AS PER CLIENT'S REQUEST DATED 10/03/2024.
48. REVISION R1 INCORPORATES CHANGES AS PER BUILDING AUTHORITY COMMENTS.
49. ORIGINAL ISSUE DATED 14/03/2024.
50. END OF NOTES.

Sr. No.	Description	Qty	Unit	Rate	Amount
1	Excavation in foundation trench	120	cum	350	42000
2	Plain cement concrete 1:4:8	45	cum	5200	234000
3	Reinforced cement concrete 1:1.5:3	60	cum	6800	408000
4	Brickwork in cement mortar 1:6	210	cum	4500	945000
5	Damp proof course	320	sqm	180	57600
6	Plastering 12 mm thick	1450	sqm	220	319000
7	Flooring with vitrified tiles	980	sqm	1200	1176000
8	Painting with emulsion paint	1450	sqm	150	217500
9	Steel reinforcement	12	MT	72000	864000
10	Doors and windows	1	lot	185000	185000
11	Sanitary fixtures	1	lot	95000	95000
12	Electrical wiring and fittings	1	lot	120000	120000
13	Plumbing and water supply	1	lot	110000	110000
14	Waterproofing to terrace	180	sqm	350	63000
15	Miscellaneous and contingencies	1	lot	50000	50000